



CSI MASTERFORMAT SECTION NUMBER	08 41 13
CSI MASTERFORMAT SECTION TITLE	ALUMINUM - FRAMED ENTRANCES & STOREFRONTS
SUN METALS SYSTEMS SERIES	SUN SERIES 600T THERMALLY BROKEN WINDOW WALL

## PART 1 GENERAL

### 1.01 SUMMARY

- A. Section Includes: Aluminum Window Wall Systems
  - 1. Sun Metals Systems; **Sun 600T Thermally Broken Aluminum Window Wall System.**
- B. Related Sections:
  - 1. Sealants: Refer to Division 7 Joint Treatment Section for sealant requirements.
  - 2. Glass and Glazing: Refer to Division 8 Glass and Glazing Section for glass and glazing requirements.
  - 3. Single Source Requirement: All products listed below shall be by the same manufacturer.
    - a. Section 08 32 13 Sliding Aluminum-Framed Glass Doors.
    - b. Section 08 44 13 Glazed Aluminum Curtain Wall.
    - c. Section 08 51 13 Aluminum Windows.

### 1.02 SYSTEM PERFORMANCE DESCRIPTION

- A. Performance Requirements: Provide aluminum window systems that comply with performance requirements indicated, as demonstrated by testing manufacturer's assemblies in accordance with test method indicated.
    - 1. Wind Loads: Completed window system shall withstand wind pressure loads normal to wall plane indicated:
      - a. Exterior Walls:
        - 1) Positive Pressure: +75
        - 2) Negative Pressure: -75
    - 2. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330 with allowable stress in accordance with AA Specifications for Aluminum Structures.
      - a. For spans less than 13'-6" (4.1m): L/175 or 3/4" (19.1mm) maximum. .
      - b. For spans greater than 13'-6" (4.1m) but less than 40'-0" (12.2m): L/175 or L/240 + 1/4" (6.4mm).
    - 3. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling Stresses on glass, joint seal failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects..
    - 4. Air Infiltration: Completed window systems shall have 0.06 CFM/FT<sup>2</sup> maximum allowable infiltration when tested in accordance with ASTM E 283 at differential static pressure of 6.24 PSF
    - 5. Water Infiltration: No uncontrolled water on indoor face of any component when tested in accordance with ASTM E 331 at a static pressure of 15 PSF
    - 6. Thermal Performance for Sun 600T Thermally Broken Aluminum Window Wall System shall be:
      - a. Condensation Resistance Factor (CRF<sub>f</sub>): A minimum of 70 when tested in accordance with AAMA 1503.1.
      - b. Thermal Transmittance U-Factor: 0.41 BTU/HR/FT<sup>2</sup>/°F or less when tested in accordance with NFRC 102.
- Note: Thermal performance depends on glass specified. U-Factor shown for system when using a 1" insulated glass unit - 1/4" clear, 1/2" air space with aluminum spacer, 1/4" clear with a low emissivity coating (e = 0.062) on surface #3.

### 1.03 SUBMITTALS

- A. General: Prepare, review, approve, and submit specified submittals in accordance with "Conditions of the Contract" and Division 1 Submittals Sections. Product data, shop drawings, samples, and similar submittals are defined in "Conditions of the Contract."
- B. Product Data: Submit product data for each type window series specified.
- C. Substitutions: Whenever substitute products are to be considered, supporting technical data, samples and test reports must be submitted ten (10) working days prior to bid date in order to make a valid comparison.
- D. Shop Drawings: Submit shop drawings showing layout, profiles, and product components, including anchorage, accessories, finish colors and textures.
- E. Samples: Submit verification samples for colors on actual aluminum substrates indicating full color range expected in installed system.
- F. Quality Assurance / Control Submittals:
  - 1. Test Reports: Submit certified test reports showing compliance with specified performance characteristics and physical properties.
- G. Closeout Submittals:
  - 1. Warranty: Submit warranty documents specified herein.
  - 2. Project Record Documents: Submit project record documents for installed materials in accordance with Division 1 Project Closeout (Project Record Documents) Section.



#### 1.04 QUALITY ASSURANCE

##### A. Qualifications:

1. Installer Qualifications: Installer experienced (as determined by contractor) to perform work of this section who has specialized in the installation of work similar to that required for this project. If requested by Owner, submit reference list of completed projects.
2. Manufacturer Qualifications: Manufacturer capable of providing field service representation during construction process.

##### B. Mock-Ups (Field Constructed):

Install at project site a job mock-up using acceptable products and manufacturer approved installation methods.

Obtain Owner's and Architect's acceptance of finish color, and workmanship standard.

##### 1. Mock-Up Size:

2. Maintenance: Maintain mock-up during construction for workmanship comparison; remove and legally dispose of mock-up when no longer required.

##### 3. Incorporation: Mock-up may be incorporated into final construction upon Owner's approval..

##### C. Pre-Installation Meetings: Conduct pre-installation meeting to verify project requirements, substrate conditions, manufacturer's installation instructions, and manufacturer's warranty requirements.

#### 1.05 PROJECT CONDITIONS / SITE CONDITIONS

- ##### A. Field Measurements: Verify actual measurements/openings by field measurements before fabrication; show recorded measurements on shop drawings. Coordinate field measurements, fabrication schedule with construction progress to avoid construction delays.

#### 1.06 WARRANTY

- ##### A. Project Warranty: Refer to "Conditions of the Contract" for project warranty provisions.

- ##### B. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by an authorized company official.

1. Warranty Period: Manufacturer's Two (2) year standard warranty commencing on the substantial date of completion for the project provided that the warranty, in no event, shall start later than six (6) months from the date of shipment by Sun Metals Systems.

**EDITOR NOTE: Longer warranty periods are available at additional cost.**

## PART 2 PRODUCTS

### 2.01 MANUFACTURERS (Acceptable Manufacturers/Products)

- ##### A. Acceptable Manufacturers: **Sun Metals Systems** **5008 Tampa West Blvd.** **Tampa, FL 33634** **Telephone: (813) 886-0240; Fax: (813) 881-0812**

1. Window Wall Framing System: **Sun 600T Thermally Broken Aluminum Window Wall System.**

##### B. Window Framing System:

1. Description: Offset flush glazed; head and sill members continuous; jambs and vertical mullions attached by screw spline joinery.
2. Components: Manufacturer's standard extruded aluminum mullions, hinged mullions, 90 degree corner posts, and indicated shapes.
3. Thermal Barrier: Provide Sun 600T Thermally Broken barrier by means of 6/6 nylon polyamide glass fiber reinforced pressure extruded bars.

### 2.02 MATERIALS

- ##### A. Extrusions: ASTM B 221 (ASTM B 221M), 6063-T6 Aluminum Alloy.

##### B. Aluminum Sheet:

1. Anodized Finish: ASTM B 209 (ASTM B 209M), 5005-H14 Aluminum Alloy, 0.050" (1.27 mm) minimum thickness.
2. Painted Finish: ASTM B 209 (ASTM B 209M), 3003-H14 Aluminum Alloy, 0.080" (1.95 mm) minimum thickness.

### 2.03 ACCESSORIES

##### A. Manufacturer's Standard Accessories:

1. Fasteners: Zinc plated steel concealed fasteners; Hardened aluminum alloys or AISI 300 series stainless steel exposed fasteners.
2. Glazing: Setting blocks, edge blocks, and spacers in accordance with ASTM C 864, shore durometer hardness as recommended by manufacturer; glazing gaskets in accordance with ASTM C 864.
3. 0.050 Aluminum Sill Flashing End Dams must have 3 point attachment.

### 2.04 RELATED MATERIALS (Specified In Other Sections)

- ##### A. Glass: Refer to Division 8 Glass and Glazing Section for glass materials.

### 2.05 FABRICATION

- ##### A. Shop Assembly: Fabricate and assemble units with joints only at intersection of aluminum members with hairline joints; rigidly secure, and sealed in accordance with manufacturer's recommendations.



## 2.06 FINISHES AND COLORS

- A. Anodized Finishing: Prepare aluminum surfaces for specified finish; apply shop finish in accordance with the following:
  - 1. Anodic Coating: Electrolytic color coating followed by an organic seal applied in accordance with the requirements of AAMA 612. Aluminum extrusions shall be produced from quality controlled billets meeting AA-6063-T6.
    - a. Exposed Surfaces shall be free of scratches and other serious blemishes.
    - b. Extrusions shall be given a caustic etch followed by an anodic oxide treatment and then sealed with an organic coating applied with An electro deposition process.
    - c. The anodized coating shall comply with all of the requirements of AAMA 612: Voluntary Specifications, Performance Requirements and Test Procedures for Combined Coatings of Anodic Oxide and Transparent Organic Coatings on Architectural Aluminum. Testing shall demonstrate the ability of the finish to resist damage from mortar, salt spray, and chemicals commonly found on construction sites, and to resist the loss of color and gloss.
    - d. Overall coating thickness for finishes shall be a minimum of 0.7 mils.
- B. High Performance Organic Coating Finish:
  - 1. Fluoropolymer Type: Factory applied two-coat 70% Kynar resin by PPG, Valspar, fluoropolymer based coating system, Polyvinylidene Fluoride (PVF-2), applied in accordance with Sun Metals Systems procedures and meeting AAMA 2605 specifications.
  - 2. Colors: Selected by Architect from the following:
    - a. Standard coating color charts.
    - b. Custom coating color charts.
    - c. Color Name and Number:
- C. Finishes Testing:
  - 1. Apply 0.5% solution NaOh, sodium hydroxide, to small area of finished sample area; leave in place for sixty minutes; lightly wipe off NaOh; Do not clean area further.
  - 2. Submit samples with test area noted on each sample.

## PART 3 EXECUTION

### 3.01 MANUFACTURER'S INSTRUCTIONS / RECOMMENDATIONS

- A. Compliance: Comply with manufacturer's product data, including product technical bulletins, installation instructions, and product carton instructions. The latest installation manual is available upon request.

### 3.02 EXAMINATION

- A. Site Verification of Conditions: Verify substrate conditions (which have been previously installed under other sections) are acceptable for product installation in accordance with manufacturer's instructions.

### 3.03 PREPARATION

- A. Adjacent Surfaces Protection: Protect adjacent work areas and finish surfaces from damage during product installation.

### 3.04 INSTALLATION

- A. General: Install manufacturer's system in accordance with shop drawings, and within specified tolerances.
  - 1. Protect aluminum members in contact with masonry, steel, concrete, or dissimilar materials using nylon pads or bituminous coating.
  - 2. Shim and brace aluminum system before anchoring to structure.
  - 3. Provide sill flashing at exterior window systems. Extend extruded flashing continuous with splice joints; set in continuous beads of sealant.
  - 4. Verify window system allows water entering system to be collected in gutters and wept to exterior. Verify weep holes are open, and metal joints are sealed in accordance with manufacturer's installation instructions.
  - 5. Locate expansion mullions where indicated on reviewed shop drawings.
  - 6. Seal metal to metal window system joints using sealant recommended by system manufacturer.

### 3.05 FIELD QUALITY CONTROL

- A. Manufacturer's Field Services: Upon request, provide manufacturer's field service consisting of site visit for inspection of product installation in accordance with manufacturer's instructions.
- B. Field Test: Conduct field test to determine water tightness of window system. Conduct test in accordance with AAMA 501.2.

### 3.06 ADJUSTING AND CLEANING

- A. Adjusting: Adjust swing doors for operation in accordance with manufacturer's recommendations.
- B. Cleaning: The General Contractor shall clean installed products in accordance with manufacturer's instructions prior to owner's acceptance, and remove construction debris from project site. Legally dispose of debris.
- C. Protection: The General Contractor shall protect the installed product's finish surfaces from damage during construction.

## END OF SECTION